



- NOTES:
1. CONTRACTOR TO VERIFY ALL DIMENSIONS. FACTORY CANNOT ASSUME ALTERATION COSTS AFTER FINAL SUBMITTAL DRAWINGS HAVE BEEN APPROVED.
  2. HOUSING, SIDE ARM TUBES, AND COUNTERWEIGHTS (12 x 12) TO BE HOT DIP GALVANIZED.
  3. STEEL OPERATOR TO HAVE DOORS IN FRONT AND BACK (ROADWAY AND COUNTERWEIGHT END).
  4. STEEL BOLLARD TO HAVE DOOR IN BACK.
  5. GALVANIZED ANCHOR BOLTS & TEMPLATE BY B & B. (Ø1.125-7 UNC X 2'-9" LONG).
  6. GASKET OR SILICON TO BE PLACED BETWEEN PIVOT PLATE ASSEMBLY & HOUSING TOP PLATE.
  7. BARRIER ARM TO HAVE MAGLOCK.
  8. .875" DIAMETER CABLE TO LOOP THROUGH 4" NOM SCH 40 PIPE.
  9. .188" SS TRUSS CABLES WITH GALVANIZED TURNBUCKLES, 2 PLACES.
  10. BARRIER ARM TO HAVE RED & WHITE REFLECTIVE STRIPES 16" WIDE AT 45°.
  11. PRODUCT SHOWN WITH OPTIONAL COMPONENTS INSTALLED.

BOLLARD ANCHOR BOLT LOCATION  
CONDUIT OPENING: 12 x 24

HOUSING ANCHOR BOLT LOCATION  
BOLTING PATTERN TYPICAL

**CR-25E Barrier**  
**DIM A = 22'-4"**  
**CLEAR OPENING = 20'-0"**

B&B ARM  
 2009 Chenault Dr #114  
 Carrollton, Tx 75006  
 800-367-0387

cr25-20FTCO.DWG